



BID BULLETIN NO. 1

DATE : May 5, 2022
TO : ALL INTERESTED BIDDERS
PROJECT : **SUPPLY, DELIVERY, INSTALLATION, TESTING AND COMMISSIONING OF ONE (1) UNIT MODULAR DPA UPS FOR SLOT MACHINE UNDER ITB NO. CB22-05-005OLO**

I. INTRODUCTION:

This Bid Bulletin is issued to clarify, supplement, modify and/or revise the particular sections in the Bidding Documents posted in PhilGEPS on May 3, 2022. The Bidders shall carefully take note of the following revisions and consider them in the preparation of their bid proposals, as they shall form part of the BIDDING DOCUMENTS.

II. INSTRUCTIONS:

Bidders have the option to update or integrate the parameters set forth in the Bid Bulletin with the specifications provided under **Section VII - Technical Specification and Section IX – Bidding Forms - Draft Purchase Contract (Terms and Condition)** to include this Bid Bulletin as part of Bidding Documents.

In either case, bidders are required to state either “Comply” or “Not Comply” against each of the individual parameters of each specification indicated in the updated **Section VII - Technical Specification and Section IX – Bidding Forms - Draft Purchase Contract (Terms and Condition)** of the Bidding Document and/or the Bid Bulletin that was made part of the submittals.

The statement of “Comply” or Not Comply” must be supported evidence in a Bidder’s Bid and cross referenced to that evidence, when applicable

III. CLARIFICATION/MODIFICATION IN THE BIDDING DOCUMENTS:

Please effect the following changes in the Bidding Documents:

**SECTION VII
TECHNICAL SPECIFICATIONS**

Page	FROM	Statement of Compliance "Comply" or "Not Comply"																																																																						
30,31, 32,33, & 34	<p>UNINTERRUPTED POWER SUPPLY (UPS). ONE (1) 8KVA N+1 MODULAR UPS, 220V, three phase. 96% power factor efficiency, 60hz, on-line double conversion technology Uninterruptible Power Supply (UPS), with Built-in battery of 15-minutes back-up time at full load capacity.</p> <table border="1"> <thead> <tr> <th colspan="2">Technical Parameters</th> </tr> <tr> <th colspan="2">Input Parameter</th> </tr> </thead> <tbody> <tr> <td>Input Voltage</td> <td>160-280V, three Phase</td> </tr> <tr> <td>Input Frequency</td> <td>60Hz</td> </tr> <tr> <td>Input Power Factor</td> <td>>0.99</td> </tr> <tr> <td>Total harmonic distortion</td> <td><3% without external filter</td> </tr> <tr> <th colspan="2">Output parameter</th> </tr> <tr> <td>Output KVA rating</td> <td>20kva</td> </tr> <tr> <td>Output KW rating</td> <td>20kw</td> </tr> <tr> <td>Output Voltage</td> <td>220v three phase</td> </tr> <tr> <td>Output Frequency</td> <td>60hz</td> </tr> <tr> <td>Output power factor</td> <td>Unity (100%)</td> </tr> <tr> <td>Output Voltage distortion</td> <td><1.5% with linear load / <3% with on linear load</td> </tr> <tr> <th colspan="2">Battery</th> </tr> <tr> <td>Type</td> <td>Maintenance free sealed lead acid</td> </tr> <tr> <td>Back-up Time</td> <td>Back-up time + 15 minutes at full load capacity</td> </tr> <tr> <td>Compliance</td> <td>ISO, UL, CE, JIS certified (US, Europe and Japan made)</td> </tr> <tr> <td>Warranty</td> <td>12 months</td> </tr> <tr> <th colspan="2">Physical</th> </tr> <tr> <td>UPS dimension in mm</td> <td>550w x 800d x 2000h (maximum)</td> </tr> <tr> <td>Weight in kgs (without Battery)</td> <td>300kgs (maximum)</td> </tr> <tr> <th colspan="2">Control indicator</th> </tr> <tr> <td colspan="2"> <ul style="list-style-type: none"> • UPS Status • Input Voltage • Frequency (input & output) • Current delivered by ups in amperes per line • Power delivered in KVA • Power delivered in kw • Battery voltage • Bypass enable/disable • Power factor </td> </tr> <tr> <th colspan="2">Environmental Requirement</th> </tr> <tr> <td>Operating condition</td> <td>0-95% non-condensing humidity, 0-4 c or in accordance with ANSI & IEC standards</td> </tr> <tr> <td>Noise level</td> <td><65 dba @ 1 meter</td> </tr> <tr> <th colspan="2">UPS Cabinet</th> </tr> <tr> <td>Degree of protection</td> <td>Ip 20</td> </tr> <tr> <th colspan="2">Standards</th> </tr> <tr> <td>Product declaration</td> <td>CE or UL</td> </tr> <tr> <td>Other Standards</td> <td>UI/ ANSI / IEC and ISO standard compliant</td> </tr> <tr> <th colspan="2">Other Specification:</th> </tr> <tr> <td colspan="2">1. The supplier shall provide to PAGCOR Maintenance and Slot Machine Department personnel the necessary training to cover comprehensive operational procedures, preventive maintenance and emergency troubleshooting.</td> </tr> <tr> <td colspan="2">2. Venue of training must be at the installation site of the UPS</td> </tr> <tr> <td colspan="2">3. Discover and operate – the operating principle of the static power supply and sub-assemblies using the system. Hands-on training regarding basic operations and maintenance of the UPS will be conducted including practical work.</td> </tr> </tbody> </table>	Technical Parameters		Input Parameter		Input Voltage	160-280V, three Phase	Input Frequency	60Hz	Input Power Factor	>0.99	Total harmonic distortion	<3% without external filter	Output parameter		Output KVA rating	20kva	Output KW rating	20kw	Output Voltage	220v three phase	Output Frequency	60hz	Output power factor	Unity (100%)	Output Voltage distortion	<1.5% with linear load / <3% with on linear load	Battery		Type	Maintenance free sealed lead acid	Back-up Time	Back-up time + 15 minutes at full load capacity	Compliance	ISO, UL, CE, JIS certified (US, Europe and Japan made)	Warranty	12 months	Physical		UPS dimension in mm	550w x 800d x 2000h (maximum)	Weight in kgs (without Battery)	300kgs (maximum)	Control indicator		<ul style="list-style-type: none"> • UPS Status • Input Voltage • Frequency (input & output) • Current delivered by ups in amperes per line • Power delivered in KVA • Power delivered in kw • Battery voltage • Bypass enable/disable • Power factor 		Environmental Requirement		Operating condition	0-95% non-condensing humidity, 0-4 c or in accordance with ANSI & IEC standards	Noise level	<65 dba @ 1 meter	UPS Cabinet		Degree of protection	Ip 20	Standards		Product declaration	CE or UL	Other Standards	UI/ ANSI / IEC and ISO standard compliant	Other Specification:		1. The supplier shall provide to PAGCOR Maintenance and Slot Machine Department personnel the necessary training to cover comprehensive operational procedures, preventive maintenance and emergency troubleshooting.		2. Venue of training must be at the installation site of the UPS		3. Discover and operate – the operating principle of the static power supply and sub-assemblies using the system. Hands-on training regarding basic operations and maintenance of the UPS will be conducted including practical work.		
Technical Parameters																																																																								
Input Parameter																																																																								
Input Voltage	160-280V, three Phase																																																																							
Input Frequency	60Hz																																																																							
Input Power Factor	>0.99																																																																							
Total harmonic distortion	<3% without external filter																																																																							
Output parameter																																																																								
Output KVA rating	20kva																																																																							
Output KW rating	20kw																																																																							
Output Voltage	220v three phase																																																																							
Output Frequency	60hz																																																																							
Output power factor	Unity (100%)																																																																							
Output Voltage distortion	<1.5% with linear load / <3% with on linear load																																																																							
Battery																																																																								
Type	Maintenance free sealed lead acid																																																																							
Back-up Time	Back-up time + 15 minutes at full load capacity																																																																							
Compliance	ISO, UL, CE, JIS certified (US, Europe and Japan made)																																																																							
Warranty	12 months																																																																							
Physical																																																																								
UPS dimension in mm	550w x 800d x 2000h (maximum)																																																																							
Weight in kgs (without Battery)	300kgs (maximum)																																																																							
Control indicator																																																																								
<ul style="list-style-type: none"> • UPS Status • Input Voltage • Frequency (input & output) • Current delivered by ups in amperes per line • Power delivered in KVA • Power delivered in kw • Battery voltage • Bypass enable/disable • Power factor 																																																																								
Environmental Requirement																																																																								
Operating condition	0-95% non-condensing humidity, 0-4 c or in accordance with ANSI & IEC standards																																																																							
Noise level	<65 dba @ 1 meter																																																																							
UPS Cabinet																																																																								
Degree of protection	Ip 20																																																																							
Standards																																																																								
Product declaration	CE or UL																																																																							
Other Standards	UI/ ANSI / IEC and ISO standard compliant																																																																							
Other Specification:																																																																								
1. The supplier shall provide to PAGCOR Maintenance and Slot Machine Department personnel the necessary training to cover comprehensive operational procedures, preventive maintenance and emergency troubleshooting.																																																																								
2. Venue of training must be at the installation site of the UPS																																																																								
3. Discover and operate – the operating principle of the static power supply and sub-assemblies using the system. Hands-on training regarding basic operations and maintenance of the UPS will be conducted including practical work.																																																																								

Page	TO	Statement of Compliance "Comply" or "Not Comply"																																																																										
30,31,32, 33,& 34	<p>UNINTERRUPTED POWER SUPPLY (UPS). ONE (1) 80KVA N+1 MODULAR UPS, Scalable up to 120KW (380/400/415V), three phase. 96% power factor efficiency, 60hz, on-line double conversion technology Uninterruptible Power Supply (UPS), with battery of 15-minutes back-up time at full load capacity.</p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th colspan="2" style="text-align: center;">Technical Parameters</th> </tr> <tr> <th colspan="2" style="text-align: center;">Input Parameter</th> </tr> </thead> <tbody> <tr> <td>Input Voltage</td> <td>380/400/415V, three Phase</td> </tr> <tr> <td>Input Frequency</td> <td>60Hz</td> </tr> <tr> <td>Input Power Factor</td> <td>0.99</td> </tr> <tr> <td>Total harmonic distortion</td> <td><3% without external filter</td> </tr> <tr> <th colspan="2" style="text-align: center;">Output parameter</th> </tr> <tr> <td>Output KVA rating</td> <td>20kva</td> </tr> <tr> <td>Output KW rating</td> <td>20kw</td> </tr> <tr> <td>Output Voltage</td> <td>380/400/415v three phase</td> </tr> <tr> <td>Output Frequency</td> <td>60hz</td> </tr> <tr> <td>Output power factor</td> <td>Unity (100%)</td> </tr> <tr> <td>Output Voltage distortion</td> <td><1.5% with linear load / <3% with on linear load</td> </tr> <tr> <th colspan="2" style="text-align: center;">Each Power Module</th> </tr> <tr> <td colspan="2"> <ul style="list-style-type: none"> Shall consist a controller Shall consist a rectifier/charger Shall consist an inverter Shall consist a static bypass switch Shall consist LED and LCD Display Shall consist Internal Mounted Fans Shall be plug in and hot swappable The UPS system shall have the capability to replace the faulty UPS module without transfer the load on by-pass if one UPS module fails. Maximum weight: 21.5kg </td> </tr> <tr> <th colspan="2" style="text-align: center;">Battery</th> </tr> <tr> <td>Type</td> <td>Maintenance free sealed lead acid</td> </tr> <tr> <td>Back-up Time</td> <td>Back-up time + 15 minutes at full load capacity</td> </tr> <tr> <td>Compliance</td> <td>ISO, UL, CE or JIS certified (US, Europe and Japan made)</td> </tr> <tr> <td>Warranty</td> <td>12 months</td> </tr> <tr> <th colspan="2" style="text-align: center;">Physical</th> </tr> <tr> <td>UPS dimension in mm</td> <td>550w x 800d x 2000h (maximum)</td> </tr> <tr> <td>Weight in kgs (without Battery)</td> <td>300kgs (maximum)</td> </tr> <tr> <th colspan="2" style="text-align: center;">Control indicator</th> </tr> <tr> <td colspan="2"> <ul style="list-style-type: none"> UPS Status Input Voltage Frequency (input & output) Current delivered by ups in amperes per line Power delivered in KVA Power delivered in kw Battery voltage Bypass enable/disable Power factor </td> </tr> <tr> <th colspan="2" style="text-align: center;">Environmental Requirement</th> </tr> <tr> <td>Operating condition</td> <td>0-95% non-condensing humidity, 0-4 c or in accordance with ANSI & IEC standards</td> </tr> <tr> <td>Noise level</td> <td><65 dba @ 1 meter</td> </tr> <tr> <th colspan="2" style="text-align: center;">UPS Cabinet</th> </tr> <tr> <td>Degree of protection</td> <td>Ip 20</td> </tr> <tr> <th colspan="2" style="text-align: center;">Standards</th> </tr> <tr> <td>Product declaration</td> <td>CE or UL</td> </tr> <tr> <td>Other Standards</td> <td>UI/ ANSI / IEC and ISO standard compliant</td> </tr> <tr> <th colspan="2" style="text-align: center;">Other Specification:</th> </tr> <tr> <td colspan="2">1. Include comprehensive power quality testing prior and after commissioning with data report duly signed by a registered electrical engineer</td> </tr> <tr> <td colspan="2">2. Submit comprehensive product catalog, brochures of the equipment being offered with complete technical specification, printed in English</td> </tr> <tr> <td colspan="2">3. Submit certificate of compliance for UPS equipment standards (IEC, UL or ANSI)</td> </tr> </tbody> </table>	Technical Parameters		Input Parameter		Input Voltage	380/400/415V, three Phase	Input Frequency	60Hz	Input Power Factor	0.99	Total harmonic distortion	<3% without external filter	Output parameter		Output KVA rating	20kva	Output KW rating	20kw	Output Voltage	380/400/415v three phase	Output Frequency	60hz	Output power factor	Unity (100%)	Output Voltage distortion	<1.5% with linear load / <3% with on linear load	Each Power Module		<ul style="list-style-type: none"> Shall consist a controller Shall consist a rectifier/charger Shall consist an inverter Shall consist a static bypass switch Shall consist LED and LCD Display Shall consist Internal Mounted Fans Shall be plug in and hot swappable The UPS system shall have the capability to replace the faulty UPS module without transfer the load on by-pass if one UPS module fails. Maximum weight: 21.5kg 		Battery		Type	Maintenance free sealed lead acid	Back-up Time	Back-up time + 15 minutes at full load capacity	Compliance	ISO, UL, CE or JIS certified (US, Europe and Japan made)	Warranty	12 months	Physical		UPS dimension in mm	550w x 800d x 2000h (maximum)	Weight in kgs (without Battery)	300kgs (maximum)	Control indicator		<ul style="list-style-type: none"> UPS Status Input Voltage Frequency (input & output) Current delivered by ups in amperes per line Power delivered in KVA Power delivered in kw Battery voltage Bypass enable/disable Power factor 		Environmental Requirement		Operating condition	0-95% non-condensing humidity, 0-4 c or in accordance with ANSI & IEC standards	Noise level	<65 dba @ 1 meter	UPS Cabinet		Degree of protection	Ip 20	Standards		Product declaration	CE or UL	Other Standards	UI/ ANSI / IEC and ISO standard compliant	Other Specification:		1. Include comprehensive power quality testing prior and after commissioning with data report duly signed by a registered electrical engineer		2. Submit comprehensive product catalog, brochures of the equipment being offered with complete technical specification, printed in English		3. Submit certificate of compliance for UPS equipment standards (IEC, UL or ANSI)		
Technical Parameters																																																																												
Input Parameter																																																																												
Input Voltage	380/400/415V, three Phase																																																																											
Input Frequency	60Hz																																																																											
Input Power Factor	0.99																																																																											
Total harmonic distortion	<3% without external filter																																																																											
Output parameter																																																																												
Output KVA rating	20kva																																																																											
Output KW rating	20kw																																																																											
Output Voltage	380/400/415v three phase																																																																											
Output Frequency	60hz																																																																											
Output power factor	Unity (100%)																																																																											
Output Voltage distortion	<1.5% with linear load / <3% with on linear load																																																																											
Each Power Module																																																																												
<ul style="list-style-type: none"> Shall consist a controller Shall consist a rectifier/charger Shall consist an inverter Shall consist a static bypass switch Shall consist LED and LCD Display Shall consist Internal Mounted Fans Shall be plug in and hot swappable The UPS system shall have the capability to replace the faulty UPS module without transfer the load on by-pass if one UPS module fails. Maximum weight: 21.5kg 																																																																												
Battery																																																																												
Type	Maintenance free sealed lead acid																																																																											
Back-up Time	Back-up time + 15 minutes at full load capacity																																																																											
Compliance	ISO, UL, CE or JIS certified (US, Europe and Japan made)																																																																											
Warranty	12 months																																																																											
Physical																																																																												
UPS dimension in mm	550w x 800d x 2000h (maximum)																																																																											
Weight in kgs (without Battery)	300kgs (maximum)																																																																											
Control indicator																																																																												
<ul style="list-style-type: none"> UPS Status Input Voltage Frequency (input & output) Current delivered by ups in amperes per line Power delivered in KVA Power delivered in kw Battery voltage Bypass enable/disable Power factor 																																																																												
Environmental Requirement																																																																												
Operating condition	0-95% non-condensing humidity, 0-4 c or in accordance with ANSI & IEC standards																																																																											
Noise level	<65 dba @ 1 meter																																																																											
UPS Cabinet																																																																												
Degree of protection	Ip 20																																																																											
Standards																																																																												
Product declaration	CE or UL																																																																											
Other Standards	UI/ ANSI / IEC and ISO standard compliant																																																																											
Other Specification:																																																																												
1. Include comprehensive power quality testing prior and after commissioning with data report duly signed by a registered electrical engineer																																																																												
2. Submit comprehensive product catalog, brochures of the equipment being offered with complete technical specification, printed in English																																																																												
3. Submit certificate of compliance for UPS equipment standards (IEC, UL or ANSI)																																																																												

BID BULLETIN NO. 1

6.	Decentralized Parallel Architecture that each module shall have its own logic control, control panel, rectifier, inverter, battery charger, static bypass and hot swappable that shall have the capability to replace the faulty UPS module without transfer the load on by-pass if one UPS module fails.
7.	Modular design consisting of freestanding metal cabinet to house up to 6 UPS power module with rated power of 20 kw
8.	Inclusion of 150kva, Isolation transformer Pri 230V Sec 400V 3 Phase
9.	Supply and Installation of Panel and Electrical Works. Supplier shall do the supply, delivery, and installation of the feeder line from Main panel to Load panel and shall provide all the necessary materials and panel(s) to complete the work for 80 KVA N+1 scalable up to 120KVA UPS, Batteries and transformer.
10.	Provision of service unit of UPS to avoid downtime.
SUPPORT PERSONNEL:	
1.	Shall be within eight (8) hours upon official notification outside Metro Manila.
CONDUCT OF SITE INSPECTION;	
1.	For the electrical materials and labor cost of the inter connection of UPS to Electrical power system of CF-Olongapo from EE room to UPS room, please coordinate with CF-Olongapo SFMO Genevieve T. Sta. Teresa and STO1 Ryan A. Agahan

Please be guided accordingly.

Please acknowledge receipt of this bid bulletin and fax it at (047) 224-2805 or email it to Allan.Ocampo@pagcor.ph.

Thank you.


MARY JANE A. MANERA
 Chairperson
 BRANCH BIDS AND AWARDS COMMITTEE (BBAC)
 CF-OLONGAPO

Received by:

 Signature over printed name
 Position: _____

 Name of Company

 Date